NAVAL ARCHITECTS-MARINE CONSULTANTS

174000 DWT DOUBLE SIDE SKIN BULK CARRIER

BOHAI SHIPBUILDING HEAVY INDUSTRY CO.,LTD.

FINISHED DESIGN

Mark	Qty	Rev.Sh.No	Sign	Date
Designed				
Checked				
Stan.Rev				
Reviewed				
Approved				

HYDROSTATIC DATA TABLES

BH410-020-005

Suitable for No. 2

Weight		Scale	
Total 20		Sheet 1	

BOHAI SHIPBUILDING HEAVY INDUSTRY CO., LTD.

NAVAL ARCHITECTS – MARINE CONSULTANTS

HYD-PACKAGE

A DnV-PILOT originate program system

HYDROSTATICS & CROSS CURVES

CURRENT HYD1 MODEL NUMBER . . . . : 12
CURRENT HYD2 MODEL NUMBER . . . . : 12

I D E N T I F I C A T I O N

ID. : 174000 DWT DOUBLE SKIN BULK CARRIER
DATE . . . . . : 2004-12-22
SIGNATURE . . . . . : FKABLL

U N I T D E F I N I T I O N S

LENGTH UNIT . . . . . : metres [m]
LENGTH UNIT CONVERSION FACTOR . . . . . : 1.0000 [m/m]

WEIGHT UNIT . . . . . : tonnes [t]
WEIGHT UNIT CONVERSION FACTOR . . . . . : 1.0000 [t/t]

P R I N C I P A L D A T A

LENGTH BETWEEN PERPENDICULARS . . . . . :	278.200 m
BREADTH MOULDED . . . . . :	45.000 m
DEPTH MOULDED . . . . . :	24.650 m
DESIGN DRAUGHT . . . . . :	16.500 m
DIST. FROM ORIGIN TO AP . . . . . :	0.000 m

A X I S D E F I N I T I O N

POSITIVE DIRECTIONS ARE: X TO STARBOARD — POSITIVE TRIM BY THE STERN
Y FORWARD — POSITIVE HEEL TO STARBOARD
Z UPWARDS

R E F E R E N C E S

DEFINITION OF GLOBAL ORIGIN

TRANSVERSE....: CENTRELINE
LONGITUDINAL..: AFTER PERPENDICULAR
VERTICAL......: BASELINE

OUTPUT REFERENCE POINT (RFP), DISTANCE FROM GLOBAL ORIGIN

TRANSVERSE....: 0.000 m : CENTRELINE
LONGITUDINAL..: 139.100 m : AMIDSHIPS (Lpp/2)
VERTICAL......: 0.000 m : BASELINE

DRAUGHT EXTREME (above RFP):

VERTICAL......: 0.000 m : BASELINE

POSITION OF MAX. SECTION (fwd of RFP):

LONGITUDINAL..: 0.000 m

A B B R E V I A T I O N S

1	DRAUGHT EXTREME .:	Extreme draught at RFP.
2	DRAUGHT RFP .....:	Draught above RFP.
3	TRIM .....:	Trim to stern in [m] .
4	DISPL TOTAL SW ..:	Total displacement in seawater. (1.025 t/m3)
5	DISPL TOTAL FW ..:	Total displacement in freshwater. (1 t/m3)
6	DISPL MLD .....:	Moulded volume of displacement.
7	TCF SBD OF RFP ..:	Transv. centre of flotation to starboard of RFP.
8	LCF FWD OF RFP ..:	Long. centre of flotation forward of RFP.
9	TCB SBD OF RFP ..:	Transv. centre of bouyancy to starboard of RFP.
10	LCB FWD OF RFP ..:	Long. centre of bouyancy forward of RFP.
11	VCB ABOVE RFP ...:	Vert. centre of bouyancy above RFP.
12	KMT .....:	Position of transverse metacentre above RFP.
13	KML .....:	Position of longitudinal metacentre above RFP.
14	IT .....:	Min. moment of inertia about neutral axis.
15	IL .....:	Max. moment of inertia about neutral axis.
16	MCT SW .....:	Moment to change trim one cm in seawater.
18	TPM SW .....:	Force to change draught one cm in seawater.
23	WPA .....:	Waterplane area.
24	WSA .....:	Projected wetted surface area.
25	CB .....:	Block coefficient = $\frac{\text{Displacement moulded}}{\text{Lbp*Draught(RFP)*Br.mld}}$
26	CM .....:	Max section coefficient = $\frac{\text{Max sectional area}}{\text{Draught(RFP)*Br.mld}}$
27	CP .....:	CB/CM
28	CW .....:	Waterplane area coefficient = $\frac{\text{Waterplane area}}{\text{Lbp*Br.mld}}$

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	2.000	2.500	3.000	3.500	4.000
4 DISP TOTAL SW .....[t]:	18911.6	23930.7	29004.2	34131.0	39305.0
5 DISP TOTAL FW .....[t]:	18450.4	23347.1	28296.8	33298.5	38346.3
6 DISP MLD .....[m3]:	18257.4	23147.8	28091.4	33087.2	38129.2
8 LCF FWD OF RFP ....[m]:	12.401	12.357	12.306	12.249	12.183
10 LCB FWD OF RFP ....[m]:	12.886	12.786	12.707	12.649	12.591
11 VCB ABOVE RFP .....[m]:	1.029	1.287	1.545	1.802	2.060
12 KMT .....[m]:	77.099	63.245	52.899	46.050	40.943
13 KML .....[m]:	2249.34	1853.57	1554.33	1351.36	1196.83
14 IT/1000 .....[m4]:	1389	1417	1443	1466	1486
15 IL/1000 .....[m4]:	41048.18	42416.12	43632.14	44701.81	45646.43
16 MCT SW .....[tm/cm]:	1512.38	1562.78	1607.58	1646.99	1681.80
18 TPM SW .....[t/cm]:	99.452	100.773	101.929	102.922	103.795
23 WPA .....[m2]:	9702.7	9831.6	9944.3	10041.2	10126.3
24 WSA .....[m2]:	10181.9	10517.4	10843.9	11161.5	11473.2
25 CB .....:	.7292	.7396	.7480	.7551	.7614
26 CP .....:	.7421	.7501	.7568	.7627	.7681
27 CM .....:	.9826	.9861	.9884	.9900	.9913
28 CW .....:	.7750	.7853	.7943	.8021	.8089
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	19883.0	24895.4	29964.2	35088.9	40259.4
0.000 [m]:	18911.6	23930.7	29004.2	34131.0	39305.0
2.000 [m]:	18107.6	23102.7	28159.6	33277.6	38445.6
4.000 [m]:	17504.3	22440.0	27452.1	32539.9	37687.2
6.000 [m]:	17401.0	22072.4	26918.2	31939.2	37050.1
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	28.293	25.604	23.539	22.093	20.976
0.000 [m]:	12.886	12.786	12.707	12.649	12.591
2.000 [m]:	-3.833	-.911	1.281	2.744	3.844
4.000 [m]:	-21.097	-15.068	-10.522	-7.454	-5.142
6.000 [m]:	-35.544	-28.224	-22.318	-17.794	-14.266
KMT [m]					
TRIM : -2.000 [m]:	73.407	60.805	51.289	44.846	40.002
0.000 [m]:	77.099	63.245	52.899	46.050	40.943
2.000 [m]:	80.064	65.355	54.397	47.182	41.819
4.000 [m]:	81.437	66.656	55.561	48.137	42.606
6.000 [m]:	76.534	65.277	56.076	48.866	43.243

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	4.500	5.000	5.500	6.000	6.500
4 DISP TOTAL SW .....[t]:	44523.6	49774.4	55060.0	60371.8	65714.8
5 DISP TOTAL FW .....[t]:	43437.6	48560.4	53717.1	58899.3	64112.0
6 DISP MLD .....[m3]:	43214.8	48332.0	53483.0	58659.8	63867.0
8 LCF FWD OF RFP ....[m]:	12.111	11.999	11.821	11.630	11.445
10 LCB FWD OF RFP ....[m]:	12.533	12.475	12.418	12.364	12.304
11 VCB ABOVE RFP .....[m]:	2.318	2.575	2.833	3.090	3.348
12 KMT .....[m]:	37.226	33.993	31.567	29.450	27.790
13 KML .....[m]:	1080.91	979.04	900.69	831.35	774.69
14 IT/1000 .....[m4]:	1504	1520	1534	1547	1559
15 IL/1000 .....[m4]:	46471.41	47237.85	47945.37	48615.64	49211.50
16 MCT SW .....[tm/cm]:	1712.19	1740.43	1766.50	1791.19	1813.15
18 TPM SW .....[t/cm]:	104.561	105.268	105.900	106.488	107.010
23 WPA .....[m2]:	10201.1	10270.0	10331.7	10389.0	10440.0
24 WSA .....[m2]:	11780.1	12083.6	12381.1	12675.1	12977.4
25 CB .....:	.7671	.7721	.7768	.7809	.7849
26 CP .....:	.7731	.7776	.7817	.7855	.7891
27 CM .....:	.9923	.9930	.9937	.9942	.9946
28 CW .....:	.8149	.8204	.8253	.8299	.8339
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	45470.9	50713.2	55992.3	61297.0	66629.1
0.000 [m]:	44523.6	49774.4	55060.0	60371.8	65714.8
2.000 [m]:	43658.2	48905.2	54193.1	59511.6	64862.5
4.000 [m]:	42887.5	48125.4	53408.3	58725.1	64078.9
6.000 [m]:	42230.6	47446.0	52717.5	58027.4	63380.9
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	20.126	19.370	18.761	18.208	17.745
0.000 [m]:	12.533	12.475	12.418	12.364	12.304
2.000 [m]:	4.656	5.360	5.885	6.337	6.691
4.000 [m]:	-3.438	-1.952	-.827	.157	.939
6.000 [m]:	-11.626	-9.383	-7.656	-6.141	-4.931
KMT [m]					
TRIM : -2.000 [m]:	36.448	33.364	31.045	29.021	27.422
0.000 [m]:	37.226	33.993	31.567	29.450	27.790
2.000 [m]:	37.931	34.560	32.062	29.886	28.173
4.000 [m]:	38.602	35.139	32.556	30.306	28.550
6.000 [m]:	39.083	35.621	33.009	30.733	28.942

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	7.000	7.500	7.750	8.000	8.250
4 DISP TOTAL SW .....[t]:	71082.6	76475.8	79180.6	81890.9	84607.0
5 DISP TOTAL FW .....[t]:	69348.9	74610.6	77249.4	79893.6	82543.4
6 DISP MLD .....[m3]:	69098.4	74354.6	76990.6	79632.1	82279.2
8 LCF FWD OF RFP ....[m]:	11.264	11.060	10.925	10.774	10.617
10 LCB FWD OF RFP ....[m]:	12.233	12.157	12.117	12.075	12.032
11 VCB ABOVE RFP .....[m]:	3.606	3.863	3.992	4.121	4.250
12 KMT .....[m]:	26.337	25.155	24.617	24.116	23.664
13 KML .....[m]:	723.971	681.328	661.685	643.205	626.210
14 IT/1000 .....[m4]:	1571	1582	1587	1593	1598
15 IL/1000 .....[m4]:	49786.21	50347.50	50624.65	50901.93	51181.33
16 MCT SW .....[tm/cm]:	1834.32	1855.00	1865.21	1875.43	1885.72
18 TPM SW .....[t/cm]:	107.507	107.972	108.200	108.429	108.659
23 WPA .....[m2]:	10488.5	10533.8	10556.1	10578.4	10600.8
24 WSA .....[m2]:	13283.1	13586.3	13737.4	13888.4	14039.2
25 CB .....:	.7885	.7919	.7935	.7951	.7966
26 CP .....:	.7924	.7956	.7971	.7986	.8000
27 CM .....:	.9950	.9954	.9955	.9956	.9958
28 CW .....:	.8378	.8414	.8432	.8450	.8468
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	71982.0	77358.8	80055.0	82756.1	85462.5
0.000 [m]:	71082.6	76475.8	79180.6	81890.9	84607.0
2.000 [m]:	70239.7	75645.5	78358.6	81078.2	83804.3
4.000 [m]:	69464.2	74882.3	77603.5	80332.4	83069.0
6.000 [m]:	68772.0	74201.7	76931.4	79670.8	82419.6
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	17.321	16.944	16.764	16.589	16.423
0.000 [m]:	12.233	12.157	12.117	12.075	12.032
2.000 [m]:	6.995	7.233	7.337	7.431	7.512
4.000 [m]:	1.623	2.178	2.428	2.658	2.865
6.000 [m]:	-3.868	-2.996	-2.601	-2.234	-1.904
KMT [m]					
TRIM : -2.000 [m]:	26.017	24.875	24.355	23.870	23.432
0.000 [m]:	26.337	25.155	24.617	24.116	23.664
2.000 [m]:	26.668	25.451	24.900	24.387	23.925
4.000 [m]:	27.014	25.772	25.207	24.682	24.207
6.000 [m]:	27.371	26.102	25.526	24.991	24.511

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	8.500	8.750	9.000	9.250	9.500
4 DISP TOTAL SW .....[t]:	87329.0	90056.9	92790.4	95529.4	98273.9
5 DISP TOTAL FW .....[t]:	85199.0	87860.4	90527.2	93199.4	95877.0
6 DISP MLD .....[m3]:	84932.0	87590.6	90254.7	92924.1	95599.0
8 LCF FWD OF RFP ....[m]:	10.458	10.288	10.109	9.920	9.719
10 LCB FWD OF RFP ....[m]:	11.987	11.938	11.887	11.833	11.778
11 VCB ABOVE RFP .....[m]:	4.378	4.507	4.636	4.765	4.894
12 KMT .....[m]:	23.256	22.868	22.504	22.172	21.872
13 KML .....[m]:	610.561	595.544	581.311	568.039	555.758
14 IT/1000 .....[m4]:	1603	1608	1613	1618	1623
15 IL/1000 .....[m4]:	51465.70	51756.63	52052.06	52349.86	52650.78
16 MCT SW .....[tm/cm]:	1896.20	1906.92	1917.81	1928.78	1939.87
18 TPM SW .....[t/cm]:	108.889	109.121	109.352	109.584	109.817
23 WPA .....[m2]:	10623.4	10645.9	10668.5	10691.1	10713.9
24 WSA .....[m2]:	14189.6	14339.8	14489.7	14639.8	14790.4
25 CB .....:	.7981	.7996	.8010	.8024	.8038
26 CP .....:	.8014	.8028	.8042	.8055	.8068
27 CM .....:	.9959	.9960	.9961	.9962	.9963
28 CW .....:	.8486	.8504	.8522	.8540	.8558
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	88174.0	90890.1	93611.0	96336.6	99067.2
0.000 [m]:	87329.0	90056.9	92790.4	95529.4	98273.9
2.000 [m]:	86537.3	89277.3	92024.3	94777.9	97538.4
4.000 [m]:	85813.5	88567.0	91329.1	94099.4	96878.2
6.000 [m]:	85178.5	87948.8	90729.9	93521.3	96322.9
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	16.265	16.108	15.954	15.805	15.660
0.000 [m]:	11.987	11.938	11.887	11.833	11.778
2.000 [m]:	7.581	7.643	7.696	7.740	7.773
4.000 [m]:	3.051	3.223	3.380	3.520	3.641
6.000 [m]:	-1.606	-1.327	-1.070	-.839	-.635
KMT [m]					
TRIM : -2.000 [m]:	23.035	22.655	22.300	21.975	21.682
0.000 [m]:	23.256	22.868	22.504	22.172	21.872
2.000 [m]:	23.507	23.108	22.734	22.393	22.086
4.000 [m]:	23.780	23.371	22.990	22.642	22.331
6.000 [m]:	24.078	23.665	23.279	22.926	22.609

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	9.750	10.000	10.250	10.500	10.750
4 DISP TOTAL SW .....[t]:	101025	103782	106546	109315	112091
5 DISP TOTAL FW .....[t]:	98561	101251	103947	106649	109358
6 DISP MLD .....[m3]:	98280	100968	103661	106359	109065
8 LCF FWD OF RFP ....[m]:	9.496	9.256	9.001	8.736	8.454
10 LCB FWD OF RFP ....[m]:	11.718	11.655	11.590	11.521	11.448
11 VCB ABOVE RFP .....[m]:	5.023	5.152	5.282	5.411	5.540
12 KMT .....[m]:	21.587	21.318	21.072	20.851	20.643
13 KML .....[m]:	544.014	532.869	522.448	512.828	503.699
14 IT/1000 .....[m4]:	1627	1632	1637	1642	1647
15 IL/1000 .....[m4]:	52964.25	53288.55	53620.69	53959.38	54319.30
16 MCT SW .....[tm/cm]:	1951.41	1963.36	1975.60	1988.08	2001.34
18 TPM SW .....[t/cm]:	110.056	110.298	110.544	110.792	111.053
23 WPA .....[m2]:	10737.1	10760.8	10784.8	10809.0	10834.4
24 WSA .....[m2]:	14941.6	15093.4	15245.8	15398.6	15553.3
25 CB .....:	.8052	.8065	.8078	.8091	.8104
26 CP .....:	.8081	.8093	.8106	.8118	.8131
27 CM .....:	.9964	.9965	.9966	.9967	.9968
28 CW .....:	.8577	.8596	.8615	.8634	.8654
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	101803	104544	107290	110040	112796
0.000 [m]:	101025	103782	106546	109315	112091
2.000 [m]:	100307	103084	105868	108659	111459
4.000 [m]:	99668	102467	105276	108093	110922
6.000 [m]:	99136	101962	104800	107651	110513
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	15.517	15.374	15.232	15.091	14.951
0.000 [m]:	11.718	11.655	11.590	11.521	11.448
2.000 [m]:	7.798	7.816	7.824	7.824	7.816
4.000 [m]:	3.749	3.844	3.925	3.990	4.044
6.000 [m]:	-.446	-.275	-.126	-.001	.110
KMT [m]					
TRIM : -2.000 [m]:	21.404	21.143	20.903	20.687	20.484
0.000 [m]:	21.587	21.318	21.072	20.851	20.643
2.000 [m]:	21.795	21.522	21.271	21.046	20.834
4.000 [m]:	22.035	21.758	21.503	21.274	21.058
6.000 [m]:	22.307	22.023	21.762	21.527	21.306

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	11.000	11.250	11.500	11.750	12.000
4 DISP TOTAL SW .....[t]:	114876	117667	120464	123270	126085
5 DISP TOTAL FW .....[t]:	112074	114797	117526	120264	123010
6 DISP MLD .....[m3]:	111779	114499	117225	119960	122703
8 LCF FWD OF RFP ....[m]:	8.150	7.821	7.463	7.080	6.675
10 LCB FWD OF RFP ....[m]:	11.370	11.289	11.203	11.113	11.018
11 VCB ABOVE RFP .....[m]:	5.670	5.799	5.929	6.059	6.189
12 KMT .....[m]:	20.447	20.268	20.107	19.958	19.818
13 KML .....[m]:	495.092	487.151	480.004	473.328	466.986
14 IT/1000 .....[m4]:	1652	1657	1662	1667	1672
15 IL/1000 .....[m4]:	54706.22	55122.31	55569.55	56042.21	56536.52
16 MCT SW .....[tm/cm]:	2015.60	2030.93	2047.40	2064.82	2083.03
18 TPM SW .....[t/cm]:	111.329	111.622	111.933	112.257	112.591
23 WPA .....[m2]:	10861.3	10889.9	10920.3	10951.9	10984.5
24 WSA .....[m2]:	15709.7	15867.5	16026.2	16185.8	16347.1
25 CB .....:	.8117	.8130	.8142	.8155	.8168
26 CP .....:	.8143	.8155	.8167	.8179	.8192
27 CM .....:	.9968	.9969	.9970	.9970	.9971
28 CW .....:	.8676	.8699	.8723	.8748	.8774
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	115559	118326	121099	123878	126665
0.000 [m]:	114876	117667	120464	123270	126085
2.000 [m]:	114269	117087	119913	122749	125595
4.000 [m]:	113761	116611	119473	122345	125228
6.000 [m]:	113387	116274	119174	122084	125002
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	14.812	14.672	14.532	14.390	14.246
0.000 [m]:	11.370	11.289	11.203	11.113	11.018
2.000 [m]:	7.799	7.775	7.742	7.701	7.652
4.000 [m]:	4.087	4.116	4.130	4.133	4.128
6.000 [m]:	.207	.288	.349	.399	.442
KMT [m]					
TRIM : -2.000 [m]:	20.293	20.117	19.959	19.813	19.676
0.000 [m]:	20.447	20.268	20.107	19.958	19.818
2.000 [m]:	20.635	20.452	20.288	20.135	19.991
4.000 [m]:	20.854	20.666	20.496	20.338	20.189
6.000 [m]:	21.097	20.903	20.728	20.563	20.407

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	12.250	12.500	12.750	13.000	13.250
4 DISP TOTAL SW .....[t]:	128908	131738	134577	137425	140283
5 DISP TOTAL FW .....[t]:	125764	128525	131295	134073	136861
6 DISP MLD .....[m3]:	125454	128212	130979	133754	136539
8 LCF FWD OF RFP ....[m]:	6.250	5.804	5.344	4.878	4.405
10 LCB FWD OF RFP ....[m]:	10.917	10.813	10.703	10.589	10.469
11 VCB ABOVE RFP .....[m]:	6.319	6.449	6.580	6.710	6.841
12 KMT .....[m]:	19.690	19.575	19.470	19.372	19.282
13 KML .....[m]:	461.054	455.609	450.463	445.440	440.635
14 IT/1000 .....[m4]:	1678	1683	1688	1693	1699
15 IL/1000 .....[m4]:	57051.89	57587.73	58136.06	58688.59	59244.33
16 MCT SW .....[tm/cm]:	2102.02	2121.76	2141.96	2162.32	2182.80
18 TPM SW .....[t/cm]:	112.934	113.287	113.645	114.003	114.362
23 WPA .....[m2]:	11018.0	11052.4	11087.3	11122.3	11157.3
24 WSA .....[m2]:	16510.7	16677.3	16846.5	17016.5	17186.6
25 CB .....:	.8180	.8193	.8206	.8219	.8231
26 CP .....:	.8204	.8216	.8228	.8241	.8253
27 CM .....:	.9972	.9972	.9973	.9973	.9974
28 CW .....:	.8801	.8829	.8856	.8884	.8912
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	129458	132256	135062	137876	140698
0.000 [m]:	128908	131738	134577	137425	140283
2.000 [m]:	128452	131319	134196	137083	139980
4.000 [m]:	128123	131030	133946	136869	139801
6.000 [m]:	127930	130868	133815	136767	139725
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	14.101	13.954	13.805	13.652	13.496
0.000 [m]:	10.917	10.813	10.703	10.589	10.469
2.000 [m]:	7.595	7.528	7.454	7.374	7.287
4.000 [m]:	4.112	4.083	4.046	4.004	3.957
6.000 [m]:	.474	.493	.505	.512	.514
KMT [m]					
TRIM : -2.000 [m]:	19.550	19.438	19.336	19.241	19.154
0.000 [m]:	19.690	19.575	19.470	19.372	19.282
2.000 [m]:	19.858	19.739	19.630	19.527	19.433
4.000 [m]:	20.051	19.926	19.812	19.704	19.604
6.000 [m]:	20.262	20.131	20.009	19.895	19.788

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	13.500	13.750	14.000	14.250	14.500
4 DISP TOTAL SW .....[t]:	143150	146026	148910	151804	154708
5 DISP TOTAL FW .....[t]:	139658	142464	145278	148101	150934
6 DISP MLD .....[m3]:	139333	142136	144946	147766	150596
8 LCF FWD OF RFP ....[m]:	3.926	3.436	2.928	2.417	1.915
10 LCB FWD OF RFP ....[m]:	10.342	10.209	10.073	9.932	9.785
11 VCB ABOVE RFP .....[m]:	6.972	7.103	7.235	7.366	7.498
12 KMT .....[m]:	19.202	19.130	19.064	19.003	18.950
13 KML .....[m]:	436.139	432.001	428.069	424.148	420.042
14 IT/1000 .....[m4]:	1704	1709	1714	1720	1725
15 IL/1000 .....[m4]:	59802.30	60368.76	60950.44	61533.40	62103.16
16 MCT SW .....[tm/cm]:	2203.36	2224.23	2245.66	2267.14	2288.13
18 TPM SW .....[t/cm]:	114.720	115.078	115.436	115.792	116.147
23 WPA .....[m2]:	11192.2	11227.1	11262.0	11296.8	11331.4
24 WSA .....[m2]:	17356.3	17525.2	17693.9	17862.3	18030.3
25 CB .....:	.8244	.8257	.8270	.8283	.8296
26 CP .....:	.8266	.8278	.8291	.8303	.8316
27 CM .....:	.9974	.9975	.9975	.9976	.9976
28 CW .....:	.8940	.8968	.8996	.9024	.9051
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	143526	146362	149207	152061	154924
0.000 [m]:	143150	146026	148910	151804	154708
2.000 [m]:	142888	145806	148729	151660	154599
4.000 [m]:	142743	145692	148646	151605	154571
6.000 [m]:	142691	145664	148640	151620	154606
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	13.337	13.176	13.013	12.845	12.673
0.000 [m]:	10.342	10.209	10.073	9.932	9.785
2.000 [m]:	7.192	7.090	6.985	6.878	6.765
4.000 [m]:	3.902	3.840	3.777	3.712	3.642
6.000 [m]:	.509	.498	.484	.468	.447
KMT [m]					
TRIM : -2.000 [m]:	19.077	19.009	18.946	18.890	18.841
0.000 [m]:	19.202	19.130	19.064	19.003	18.950
2.000 [m]:	19.348	19.273	19.202	19.137	19.079
4.000 [m]:	19.513	19.432	19.355	19.284	19.221
6.000 [m]:	19.691	19.602	19.519	19.441	19.370

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	14.750	15.000	15.250	15.500	15.750
4 DISP TOTAL SW .....[t]:	157621	160540	163465	166398	169339
5 DISP TOTAL FW .....[t]:	153777	156624	159478	162339	165209
6 DISP MLD .....[m3]:	153435	156280	159130	161988	164855
8 LCF FWD OF RFP ....[m]:	1.437	.998	.595	.224	-.116
10 LCB FWD OF RFP ....[m]:	9.633	9.480	9.326	9.170	9.012
11 VCB ABOVE RFP .....[m]:	7.630	7.762	7.894	8.026	8.158
12 KMT .....[m]:	18.905	18.863	18.826	18.795	18.772
13 KML .....[m]:	415.644	411.205	406.764	402.326	397.893
14 IT/1000 .....[m4]:	1730	1735	1740	1745	1750
15 IL/1000 .....[m4]:	62638.63	63109.51	63524.28	63895.10	64235.87
16 MCT SW .....[tm/cm]:	2307.86	2325.21	2340.49	2354.15	2366.71
18 TPM SW .....[t/cm]:	116.491	116.791	117.056	117.295	117.522
23 WPA .....[m2]:	11365.0	11394.3	11420.1	11443.4	11465.5
24 WSA .....[m2]:	18197.5	18363.0	18526.9	18689.4	18850.5
25 CB .....:	.8309	.8322	.8335	.8348	.8361
26 CP .....:	.8329	.8342	.8354	.8367	.8379
27 CM .....:	.9976	.9977	.9977	.9978	.9978
28 CW .....:	.9078	.9102	.9122	.9141	.9159
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	157795	160674	163563	166461	169372
0.000 [m]:	157621	160540	163465	166398	169339
2.000 [m]:	157547	160497	163451	166412	169379
4.000 [m]:	157544	160520	163498	166480	169467
6.000 [m]:	157597	160590	163585	166583	169585
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	12.496	12.317	12.137	11.954	11.770
0.000 [m]:	9.633	9.480	9.326	9.170	9.012
2.000 [m]:	6.648	6.530	6.411	6.291	6.169
4.000 [m]:	3.568	3.494	3.419	3.342	3.262
6.000 [m]:	.423	.397	.369	.340	.308
KMT [m]					
TRIM : -2.000 [m]:	18.801	18.764	18.731	18.706	18.687
0.000 [m]:	18.905	18.863	18.826	18.795	18.772
2.000 [m]:	19.029	18.982	18.939	18.903	18.873
4.000 [m]:	19.164	19.112	19.063	19.020	18.983
6.000 [m]:	19.307	19.247	19.192	19.143	19.101

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	16.000	16.250	16.500	16.750	17.000
4 DISP TOTAL SW .....[t]:	172285	175234	178187	181146	184113
5 DISP TOTAL FW .....[t]:	168083	170960	173841	176728	179622
6 DISP MLD .....[m3]:	167726	170600	173478	176362	179253
8 LCF FWD OF RFP ....[m]:	-.425	-.700	-.942	-1.137	-1.306
10 LCB FWD OF RFP ....[m]:	8.853	8.695	8.536	8.379	8.223
11 VCB ABOVE RFP .....[m]:	8.290	8.422	8.554	8.686	8.818
12 KMT .....[m]:	18.752	18.734	18.720	18.711	18.706
13 KML .....[m]:	393.452	389.022	384.625	380.487	376.372
14 IT/1000 .....[m4]:	1754	1759	1764	1768	1772
15 IL/1000 .....[m4]:	64571.28	64905.98	65239.89	65571.17	65879.07
16 MCT SW .....[tm/cm]:	2379.06	2391.40	2403.70	2415.90	2427.25
18 TPM SW .....[t/cm]:	117.745	117.966	118.185	118.399	118.599
23 WPA .....[m2]:	11487.3	11508.9	11530.3	11551.1	11570.6
24 WSA .....[m2]:	19010.5	19169.3	19327.0	19482.6	19636.2
25 CB .....:	.8374	.8386	.8398	.8410	.8423
26 CP .....:	.8392	.8404	.8416	.8428	.8440
27 CM .....:	.9978	.9979	.9979	.9979	.9979
28 CW .....:	.9176	.9193	.9210	.9227	.9242
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	172289	175213	178142	181083	184034
0.000 [m]:	172285	175234	178187	181146	184113
2.000 [m]:	172348	175320	178295	181273	184255
4.000 [m]:	172455	175445	178437	181431	184428
6.000 [m]:	172589	175593	178599	181607	184615
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	11.584	11.398	11.213	11.030	10.848
0.000 [m]:	8.853	8.695	8.536	8.379	8.223
2.000 [m]:	6.047	5.925	5.803	5.681	5.560
4.000 [m]:	3.182	3.102	3.022	2.941	2.860
6.000 [m]:	.274	.240	.205	.168	.130
KMT [m]					
TRIM : -2.000 [m]:	18.672	18.661	18.652	18.649	18.651
0.000 [m]:	18.752	18.734	18.720	18.711	18.706
2.000 [m]:	18.846	18.822	18.801	18.786	18.775
4.000 [m]:	18.950	18.920	18.893	18.872	18.856
6.000 [m]:	19.062	19.027	18.995	18.970	18.950

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	17.250	17.500	17.750	18.000	18.200
4 DISP TOTAL SW .....[t]:	187082	190055	193033	196015	198406
5 DISP TOTAL FW .....[t]:	182519	185420	188324	191234	193566
6 DISP MLD .....[m3]:	182148	185045	187947	190854	193184
8 LCF FWD OF RFP ....[m]:	-1.465	-1.610	-1.733	-1.830	-1.890
10 LCB FWD OF RFP ....[m]:	8.070	7.919	7.769	7.622	7.508
11 VCB ABOVE RFP .....[m]:	8.950	9.082	9.214	9.346	9.451
12 KMT .....[m]:	18.704	18.705	18.708	18.715	18.723
13 KML .....[m]:	372.267	368.191	364.160	360.282	357.274
14 IT/1000 .....[m4]:	1776	1780	1784	1788	1791
15 IL/1000 .....[m4]:	66165.30	66439.43	66711.07	66982.31	67193.59
16 MCT SW .....[tm/cm]:	2437.79	2447.89	2457.90	2467.90	2475.68
18 TPM SW .....[t/cm]:	118.789	118.973	119.153	119.330	119.466
23 WPA .....[m2]:	11589.2	11607.1	11624.7	11641.9	11655.2
24 WSA .....[m2]:	19789.6	19942.7	20095.6	20248.3	20370.3
25 CB .....:	.8435	.8446	.8458	.8470	.8479
26 CP .....:	.8452	.8463	.8475	.8486	.8495
27 CM .....:	.9980	.9980	.9980	.9981	.9981
28 CW .....:	.9257	.9272	.9286	.9299	.9310
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	186989	189949	192915	195889	198273
0.000 [m]:	187082	190055	193033	196015	198406
2.000 [m]:	187238	190224	193211	196201	198596
4.000 [m]:	187425	190423	193422	196423	198824
6.000 [m]:	187624	190634	193644	196655	199063
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	10.669	10.491	10.315	10.143	10.008
0.000 [m]:	8.070	7.919	7.769	7.622	7.508
2.000 [m]:	5.440	5.321	5.203	5.087	4.997
4.000 [m]:	2.780	2.699	2.619	2.539	2.475
6.000 [m]:	.091	.052	.012	-.029	-.061
KMT [m]					
TRIM : -2.000 [m]:	18.654	18.660	18.668	18.680	18.691
0.000 [m]:	18.704	18.705	18.708	18.715	18.723
2.000 [m]:	18.767	18.761	18.759	18.761	18.766
4.000 [m]:	18.843	18.832	18.824	18.821	18.822
6.000 [m]:	18.932	18.917	18.904	18.897	18.895

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	18.250	18.500	18.750	19.000	19.250
4 DISP TOTAL SW .....[t]:	199004	201996	204992	207992	210996
5 DISP TOTAL FW .....[t]:	194150	197069	199992	202919	205850
6 DISP MLD .....[m3]:	193766	196683	199603	202527	205455
8 LCF FWD OF RFP ....[m]:	-1.903	-1.966	-2.017	-2.054	-2.085
10 LCB FWD OF RFP ....[m]:	7.480	7.340	7.203	7.070	6.939
11 VCB ABOVE RFP .....[m]:	9.478	9.609	9.741	9.873	10.005
12 KMT .....[m]:	18.725	18.738	18.753	18.770	18.790
13 KML .....[m]:	356.523	352.801	349.133	345.528	341.990
14 IT/1000 .....[m4]:	1792	1795	1799	1802	1805
15 IL/1000 .....[m4]:	67245.34	67498.72	67743.35	67980.74	68212.79
16 MCT SW .....[tm/cm]:	2477.59	2486.92	2495.94	2504.68	2513.23
18 TPM SW .....[t/cm]:	119.500	119.663	119.819	119.971	120.119
23 WPA .....[m2]:	11658.5	11674.4	11689.7	11704.5	11718.9
24 WSA .....[m2]:	20400.8	20553.1	20705.3	20857.2	21009.1
25 CB .....:	.8481	.8492	.8503	.8515	.8525
26 CP .....:	.8497	.8508	.8519	.8530	.8541
27 CM .....:	.9981	.9981	.9981	.9982	.9982
28 CW .....:	.9313	.9325	.9338	.9349	.9361
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	198870	201856	204848	207844	210844
0.000 [m]:	199004	201996	204992	207992	210996
2.000 [m]:	199195	202192	205191	208193	211199
4.000 [m]:	199424	202427	205430	208435	211442
6.000 [m]:	199666	202677	205688	208700	211712
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	9.975	9.810	9.648	9.489	9.333
0.000 [m]:	7.480	7.340	7.203	7.070	6.939
2.000 [m]:	4.974	4.863	4.755	4.648	4.545
4.000 [m]:	2.460	2.381	2.304	2.228	2.154
6.000 [m]:	-.070	-.111	-.153	-.194	-.236
KMT [m]					
TRIM : -2.000 [m]:	18.694	18.711	18.730	18.751	18.774
0.000 [m]:	18.725	18.738	18.753	18.770	18.790
2.000 [m]:	18.767	18.776	18.787	18.801	18.818
4.000 [m]:	18.822	18.827	18.835	18.846	18.859
6.000 [m]:	18.894	18.895	18.899	18.907	18.918

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	19.500	19.750	20.000	20.250	20.500
4 DISP TOTAL SW .....[t]:	214004	217016	220033	223052	226074
5 DISP TOTAL FW .....[t]:	208784	211723	214666	217612	220560
6 DISP MLD .....[m3]:	208386	211322	214263	217206	220151
8 LCF FWD OF RFP ....[m]:	-2.106	-2.117	-2.117	-2.113	-2.105
10 LCB FWD OF RFP ....[m]:	6.812	6.689	6.570	6.454	6.340
11 VCB ABOVE RFP .....[m]:	10.137	10.269	10.400	10.532	10.664
12 KMT .....[m]:	18.813	18.838	18.866	18.896	18.928
13 KML .....[m]:	338.523	335.132	331.816	328.556	325.348
14 IT/1000 .....[m4]:	1808	1811	1814	1816	1819
15 IL/1000 .....[m4]:	68437.86	68654.25	68861.77	69065.82	69267.07
16 MCT SW .....[tm/cm]:	2521.52	2529.50	2537.14	2544.66	2552.08
18 TPM SW .....[t/cm]:	120.262	120.399	120.529	120.657	120.782
23 WPA .....[m2]:	11732.9	11746.2	11758.9	11771.4	11783.6
24 WSA .....[m2]:	21160.9	21312.5	21463.9	21615.3	21766.7
25 CB .....:	.8536	.8547	.8557	.8568	.8578
26 CP .....:	.8551	.8562	.8572	.8583	.8593
27 CM .....:	.9982	.9982	.9983	.9983	.9983
28 CW .....:	.9372	.9383	.9393	.9403	.9413
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	213850	216861	219877	222896	225918
0.000 [m]:	214004	217016	220033	223052	226074
2.000 [m]:	214207	217219	220235	223253	226274
4.000 [m]:	214451	217463	220477	223494	226512
6.000 [m]:	214724	217737	220751	223766	226784
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	9.182	9.034	8.891	8.751	8.614
0.000 [m]:	6.812	6.689	6.570	6.454	6.340
2.000 [m]:	4.444	4.347	4.253	4.161	4.072
4.000 [m]:	2.081	2.011	1.943	1.877	1.812
6.000 [m]:	-.277	-.319	-.360	-.399	-.437
KMT [m]					
TRIM : -2.000 [m]:	18.800	18.828	18.859	18.891	18.925
0.000 [m]:	18.813	18.838	18.866	18.896	18.928
2.000 [m]:	18.837	18.860	18.886	18.914	18.944
4.000 [m]:	18.876	18.897	18.920	18.946	18.974
6.000 [m]:	18.931	18.949	18.971	18.994	19.020

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	20.750	20.953	21.000	21.250	21.500
4 DISP TOTAL SW .....[t]:	229099	231556	232126	235159	238193
5 DISP TOTAL FW .....[t]:	223511	225909	226465	229423	232384
6 DISP MLD .....[m3]:	223099	225494	226050	229005	231963
8 LCF FWD OF RFP ....[m]:	-2.093	-2.079	-2.074	-2.049	-2.022
10 LCB FWD OF RFP ....[m]:	6.228	6.140	6.120	6.017	5.915
11 VCB ABOVE RFP .....[m]:	10.796	10.902	10.927	11.059	11.190
12 KMT .....[m]:	18.961	18.989	18.997	19.035	19.076
13 KML .....[m]:	322.188	319.666	319.100	316.116	313.170
14 IT/1000 .....[m4]:	1822	1824	1824	1826	1829
15 IL/1000 .....[m4]:	69465.54	69624.36	69660.15	69848.96	70035.43
16 MCT SW .....[tm/cm]:	2559.39	2565.24	2566.56	2573.51	2580.39
18 TPM SW .....[t/cm]:	120.906	121.005	121.027	121.143	121.258
23 WPA .....[m2]:	11795.7	11805.3	11807.5	11818.8	11830.0
24 WSA .....[m2]:	21918.1	22041.0	22069.4	22220.6	22371.9
25 CB .....:	.8588	.8596	.8598	.8608	.8618
26 CP .....:	.8603	.8611	.8613	.8622	.8632
27 CM .....:	.9983	.9983	.9983	.9984	.9984
28 CW .....:	.9422	.9430	.9432	.9441	.9450
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	228943	231402	231972	235007	238044
0.000 [m]:	229099	231556	232126	235159	238193
2.000 [m]:	229297	231753	232322	235353	238385
4.000 [m]:	229533	231987	232555	235583	238612
6.000 [m]:	229802	232254	232822	235845	238870
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	8.479	8.371	8.347	8.221	8.097
0.000 [m]:	6.228	6.140	6.120	6.017	5.915
2.000 [m]:	3.984	3.915	3.899	3.819	3.741
4.000 [m]:	1.749	1.699	1.688	1.631	1.576
6.000 [m]:	-.474	-.504	-.511	-.545	-.578
KMT [m]					
TRIM : -2.000 [m]:	18.960	18.990	18.998	19.038	19.081
0.000 [m]:	18.961	18.989	18.997	19.035	19.076
2.000 [m]:	18.975	19.002	19.009	19.047	19.087
4.000 [m]:	19.004	19.030	19.036	19.073	19.111
6.000 [m]:	19.048	19.072	19.078	19.115	19.155

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	21.750	22.000	22.250	22.500	22.750
4 DISP TOTAL SW .....[t]:	241230	244268	247309	250355	253403
5 DISP TOTAL FW .....[t]:	235346	238310	241278	244248	247223
6 DISP MLD .....[m3]:	234922	237884	240848	243816	246787
8 LCF FWD OF RFP ....[m]:	-1.992	-1.961	-1.925	-1.884	-1.840
10 LCB FWD OF RFP ....[m]:	5.815	5.717	5.622	5.532	5.444
11 VCB ABOVE RFP .....[m]:	11.322	11.453	11.585	11.716	11.847
12 KMT .....[m]:	19.117	19.160	19.204	19.252	19.301
13 KML .....[m]:	310.264	307.398	304.604	301.890	299.242
14 IT/1000 .....[m4]:	1831	1833	1835	1838	1840
15 IL/1000 .....[m4]:	70219.94	70402.80	70582.39	70758.10	70930.32
16 MCT SW .....[tm/cm]:	2587.18	2593.92	2600.54	2607.01	2613.36
18 TPM SW .....[t/cm]:	121.371	121.482	121.592	121.698	121.802
23 WPA .....[m2]:	11841.0	11851.9	11862.6	11873.0	11883.2
24 WSA .....[m2]:	22523.0	22674.2	22825.4	22976.5	23127.6
25 CB .....:	.8628	.8637	.8647	.8656	.8665
26 CP .....:	.8642	.8651	.8660	.8669	.8678
27 CM .....:	.9984	.9984	.9984	.9985	.9985
28 CW .....:	.9458	.9467	.9476	.9484	.9492
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	241082	244120	247167	250220	253273
0.000 [m]:	241230	244268	247309	250355	253403
2.000 [m]:	241419	244452	247493	250539	253585
4.000 [m]:	241642	244671	247707	250749	253790
6.000 [m]:	241896	244920	247910	250856	253761
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	7.975	7.857	7.744	7.636	7.528
0.000 [m]:	5.815	5.717	5.622	5.532	5.444
2.000 [m]:	3.663	3.586	3.511	3.441	3.374
4.000 [m]:	1.521	1.465	1.412	1.363	1.317
6.000 [m]:	-.610	-.641	-.652	-.635	-.594
KMT [m]					
TRIM : -2.000 [m]:	19.123	19.166	19.214	19.266	19.317
0.000 [m]:	19.117	19.160	19.204	19.252	19.301
2.000 [m]:	19.126	19.166	19.211	19.261	19.311
4.000 [m]:	19.149	19.187	19.231	19.280	19.328
6.000 [m]:	19.191	19.216	19.133	18.938	18.683

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]		
3 DRAUGHT RFP .....[m]:	23.000	23.250	23.500	23.750	24.000
4 DISP TOTAL SW .....[t]:	256454	259507	262563	265620	268680
5 DISP TOTAL FW .....[t]:	250199	253178	256159	259142	262127
6 DISP MLD .....[m3]:	249761	252737	255715	258695	261677
8 LCF FWD OF RFP ....[m]:	-1.792	-1.742	-1.688	-1.632	-1.573
10 LCB FWD OF RFP ....[m]:	5.359	5.276	5.195	5.117	5.041
11 VCB ABOVE RFP .....[m]:	11.979	12.110	12.241	12.372	12.503
12 KMT .....[m]:	19.352	19.405	19.459	19.514	19.571
13 KML .....[m]:	296.648	294.099	291.593	289.128	286.703
14 IT/1000 .....[m4]:	1842	1844	1846	1847	1849
15 IL/1000 .....[m4]:	71099.42	71265.37	71427.99	71587.52	71744.18
16 MCT SW .....[tm/cm]:	2619.59	2625.70	2631.69	2637.57	2643.34
18 TPM SW .....[t/cm]:	121.904	122.004	122.101	122.196	122.289
23 WPA .....[m2]:	11893.1	11902.8	11912.3	11921.6	11930.7
24 WSA .....[m2]:	23278.6	23429.7	23580.7	23731.7	23882.7
25 CB .....:	.8674	.8683	.8692	.8701	.8709
26 CP .....:	.8687	.8696	.8705	.8714	.8722
27 CM .....:	.9985	.9985	.9985	.9985	.9985
28 CW .....:	.9500	.9508	.9515	.9523	.9530
DISP TOTAL SW [t]					
TRIM : -2.000 [m]:	256318	259346	262355	265348	268327
0.000 [m]:	256454	259507	262563	265620	268680
2.000 [m]:	256624	259644	262640	265615	268573
4.000 [m]:	256824	259771	262570	265247	267829
6.000 [m]:	256629	259372	261921	264305	266555
LCB FWD OF RFP [m]					
TRIM : -2.000 [m]:	7.416	7.299	7.181	7.062	6.941
0.000 [m]:	5.359	5.276	5.195	5.117	5.041
2.000 [m]:	3.311	3.257	3.216	3.187	3.168
4.000 [m]:	1.274	1.267	1.320	1.422	1.563
6.000 [m]:	-.534	-.432	-.269	-.053	.207
KMT [m]					
TRIM : -2.000 [m]:	19.364	19.340	19.198	18.958	18.642
0.000 [m]:	19.352	19.405	19.459	19.514	19.571
2.000 [m]:	19.355	19.325	19.173	18.919	18.585
4.000 [m]:	19.370	19.318	19.107	18.764	18.318
6.000 [m]:	18.420	18.170	17.917	17.658	17.390

HYDROSTATICS (SPLINE)	HEEL : 0.000 [Deg]		TRIM : 0.000 [m]
3 DRAUGHT RFP .....[m]:	24.250	24.500	24.650
4 DISP TOTAL SW .....[t]:	271741	274805	276644
5 DISP TOTAL FW .....[t]:	265113	268102	269896
6 DISP MLD .....[m3]:	264661	267647	269439
8 LCF FWD OF RFP ....[m]:	-1.512	-1.448	-1.408
10 LCB FWD OF RFP ....[m]:	4.966	4.894	4.851
11 VCB ABOVE RFP .....[m]:	12.634	12.765	12.844
12 KMT .....[m]:	19.629	19.688	19.724
13 KML .....[m]:	284.318	281.973	280.584
14 IT/1000 .....[m4]:	1851	1853	1854
15 IL/1000 .....[m4]:	71898.19	72049.76	72139.63
16 MCT SW .....[tm/cm]:	2649.02	2654.60	2657.91
18 TPM SW .....[t/cm]:	122.381	122.470	122.523
23 WPA .....[m2]:	11939.6	11948.3	11953.5
24 WSA .....[m2]:	24033.6	24184.6	24275.1
25 CB .....:	.8718	.8726	.8731
26 CP .....:	.8730	.8739	.8744
27 CM .....:	.9986	.9986	.9986
28 CW .....:	.9537	.9544	.9548
DISP TOTAL SW [t]			
TRIM : -2.000 [m]:	271295	274256	276030
0.000 [m]:	271741	274805	276644
2.000 [m]:	271519	274456	276216
4.000 [m]:	270340	272807	274277
6.000 [m]:	268702	270776	271997
LCB FWD OF RFP [m]			
TRIM : -2.000 [m]:	6.818	6.695	6.620
0.000 [m]:	4.966	4.894	4.851
2.000 [m]:	3.156	3.150	3.148
4.000 [m]:	1.733	1.922	2.040
6.000 [m]:	.502	.824	1.028
KMT [m]			
TRIM : -2.000 [m]:	18.269	17.862	17.609
0.000 [m]:	19.629	19.688	19.724
2.000 [m]:	18.192	17.763	17.497
4.000 [m]:	17.796	17.227	16.874
6.000 [m]:	17.111	16.818	16.634